8	Supplying and Drawing 3 core Flat PVC Shalted Submersible Pump Cable Manufactured with Electrolytic Grade Copper with Flexible copper conductor to table 3 class 5 of IS 8130-1984 and Virgen PVC insulation and Sheeated Suitable for working Voltage Upto 1100 Volts complete as per specifications.	Mtr	3100.00	159.50	Rupees One Hundred Fifty Nine and Fifty Paise Only
9	Supplying and fixing 50mm Non Return Vavle of vertical type of approved make including cost of all materials labour HOM of equipment with all leads Complete as per Specifcation	No.s	5.00	1145.00	Rupees One Thousand One Hundred Forty Five Only
10	Supplying and fixing 50mm GM Gae Vavle Complete as per Specifcation	No.s	5.00	1600.00	Rupees One Thousand Six Hundred Only
11	Supplying and fixing 160mm Borewell cap with clampset Complete as per Specifcation	No.s	5.00	690.00	Rupees Six Hundred Ninety Only
12	Supplying and fixing 50mm GI Union Complete as per Specifcation	No.s	5.00	223.70	Rupees Two Hundred Twenty Three and Seventy Paise Only
13	Supplying and fixing 50mm GI Elbow Complete as per Specifcation	No.s	15.00	111.80	Rupees One Hundred Eleven and Eighty Paise Only
14	Supplying and fixing 50mm GI coller Heavy duty Complete as per Specifcation	No.s	250.00	84.80	Rupees Eighty Four and Eighty Paise Only
15	Supplying and delivery at site brand new star / Essen / Lotus / Sun shines / Adharsh / GK Controls best indigenous make combined energy meter cum control panel board unit of size 1200x600x350mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for opration on 3ph, 50 hz, 380/440 volts, AC supply with spring loaded latch, locking device with a key ribs should be provided inside the door canopy apron and louvers ventilators shall be provided the combined energy meter cum control panel board unit suitable for operation on 3ph, 50 hz, 380/440 volts AC supply shall be consists etc., complete the panel board shall be consist etc., complete the panel board shall be fabricated on single unit in the above componenets panel board for suitable pumpset with star delta staretr out door type 10hp to 15 hp Complete as per Specifcation	No.s	5.00	10000.00	Rupees Ten Thousand Only
16	Providing and fixing of 50mm G.I pipe 'C' class heavy duty foe erection of submersible pumpset Complete as per Specifcation	Mtr	1450.00	374.00	Rupees Three Hundred Seventy Four Only

Technical Manager (TM-2)
KRIDL, Dasarahalli Zone, Bangalore

Signature of the Contractor

Executive Engineer